

Republic of the Philippines
DEPARTMENT OF EDUCATION
 Region VII, Central Visayas
DIVISION OF BOHOL
 City of Tagbilaran

REQUEST FOR QUOTATION

RFQ NO.: 2020-11-12311
 DATE: 11-20-20

Name of Company: _____
 Address: _____
 Business Permit No. _____
 TIN No. _____

Please quote your best offer for the item described below, subject to the Terms and Conditions provided at the dorsal portion of this request for quotation.

Submit your quotation duly signed by you or your duly representative and copies of the following eligibility requirements not later than _____.

1. DTI/SEC Registration
2. Business Permit
3. Latest Annual Income Tax/EFPS
4. Certificate of PhilGEPS Registration
5. Other Supporting Documents

Sealed Quotations may be submitted or mailed at DepEd-Division Office, Division of Bohol, CPG Avenue, Tagbilaran City.


MARINA S. SALAMANCA
 BAC Chairperson

After having carefully read and accepted the Terms and Conditions, I/we submit your quotation/s for the item/s as follows:

Item/Description	QTY	Unit	Approved Budget for the Contract	OFFER					
				PRICE			Compliance with Technical Specifications (Please Check)		REMARKS
				QTY	Unit Price	Total Price	Yes	No	
Renovation of Main Gate and Ground Improvement of DepEd Division of Bohol. (Total Cost = Material Cost + 30% Labor Cost)									
Earthworks									
Gravel Bedding G-1	20	cu.m.	36,400.00						
Select Fill	3	cu.m.	585.00						
Excavation	3.2	cu.m.	960.00						
Demolition of Old Gate & Landscape	1	lot	5,000.00						
Concreting Works									
Footing (COLUMNS)	0.96	cu.m.							
Portland Cement	9	bag	3,042.00						
Crushed Gravel 1"	1	cu.m.	1,690.00						
Washed Sand	0.50	cu.m.	845.00						
Columns	2.12	cu.m.							
Portland Cement	20	bag	6,760.00						
Crushed Gravel ¾"	2.25	cu.m.	3,802.50						
Washed Sand	1.25	cu.m.	2,112.50						
Roofdeck & Slab on Grade	0.45	cu.m.							
Portland Cement	5	bag	1,690.00						
Crushed Gravel 1"	0.50	cu.m.	845.00						
Washed Sand	0.25	cu.m.	422.50						
Beam	0.28	cu.m.							
Portland Cement	3	bag	1,014.00						
Crushed Gravel 1"	0.50	cu.m.	845.00						
Washed Sand	0.25	cu.m.	422.50						
Ramp on Fill (both sides)	6	cu.m.							
Portland Cement	54	bag	18,252.00						
Crushed Gravel 1"	6	cu.m.	10,140.00						
Washed Sand	3	cu.m.	5,070.00						

Rebar Works									
Deformed Round Bars, Grade 40	574.48	kg.	33,607.08						
G.I. Tie Wire	12	kg.	936.00						
Formworks									
Coco Lumber	93.327	bd.ft.	2,426.50						
Plywood Ordinary, 1/4" x 4' x 8'	8	pc.	3,952.00						
CWN, Assorted	2	kg	156.00						
Masonry Works									
Masonry Wall									
CHB 4" thk	19.50	sq.m.							
Portland Cement	244	pc.	5,075.20						
Washed Sand	10	bag	3,380.00						
10mm x 6m RSB	1	cu.m.	1,820.00						
G.I. Tie Wire	26	kg.	1,521.00						
Plastering	1	kg.	78.00						
Portland Cement	38	sq.m.							
Washed Sand	13	bag	4,394.00						
Decorative Bricks (Mactan Stone)	2	cu.m.	3,640.00						
Portland Cement	19.50	sq.m.	16,477.50						
Washed Sand	7	bag	2,366.00						
	1	cu.m.	1,820.00						
Steel Works									
Steel Rectangular Hollow Section 2" x 4"	18	pc.	28,080.00						
Steel Rectangular Hollow Section 2" x 2"	23	pc.	17,342.00						
L 50 x 50 x 3mm	5	pc.	5,200.00						
Flat Bar 4mm x 50mm x 6m	2	pc.	1,404.00						
Gate Accessories with Rollers	2	pc.	9,100.00						
Stainless DepEd logo design (1.5 thk)	1	lot	15,600.00						
Welding Rod	25	kg.	2,177.50						
Electrical Works									
Roughing-ins									
Electrical Conduit uPVC, 20mmØ	12	pc.	1,435.20						
Junction Box, 4" x 4" G.I.	6	pc.	241.80						
Utility Box, 2" x 4" G.I.	6	pc.	234.00						
Wires & Fixtures									
5.5 mm ² THHN Wire	50	m	1,365.00						
3.5 mm ² THHN Wire	50	m	910.00						
Duplex Convenience Outlet, Grounding Type, 20A, 230V	1	pc.	342.94						
Single Pole Wall Switch in One Switch Plate (10 AMP, 230V)	2	pc.	253.97						
1-18W, 230V, 60Hz AC, Compact Fluorescent Lighting Fixture with Medium Base Keyless Type Porcelain Receptacle	1	set	585.00						
40W Lights on 300mm dia Globe Diffuser with stand	2	set	2,470.00						
Panel Box, Flush Type, 4 Branches	1	set	1,563.58						
Circuit Breaker, 20A 2P	2	set	813.80						
Electrical Tape	5	pc	243.75						
Tile Works									
Floor & Counter									
Glazed Wall Tiles 60cm x 60cm	3.45	sq.m.							
Tile Adhesive 25 kg/bag	12	pc.	3,120.00						
Tile Trim 6mm	2	bag	582.66						
Tile Grout 5 kg/bag	2	pc.	254.15						
	1	bag	195.00						
Painting Works									
Neutralizer	3	gal	2,195.70						
Latex, Flat	6	gal	4,290.00						
Masonry Putty	3	gal	2,145.00						
Latex, Semi Gloss	7	gal	5,005.00						
Acri Color	4	qrt	1,040.00						
Steel Surfaces									
Primer, Red Oxide	171.40	sq.m.							
Gloss, Acrylic Paint	5	gal	3,482.05						
	8	gal	5,891.60						
TOTAL			299,110.97						
x-x-x-x-x-x-x-x									
Purpose: For the renovation of old main gate and construction of covered walkway of DepEd Division of Bohol office building.									

(Signature Over Printed Name)